



Image source: Architectus

Barker College Maths Hub



*Excellence in Timber Design
Commercial Buildings*



Kieran Hayes

Senior Technical Engineer
CPEng MIEAust NER, Passiv
Haus Designer



Project team

Client:  **Barker**
College

Architect: **architectus**

Builder: **Buildcorp**


Structural Engineer: **TTW** Taylor
Thomson
Whitting

CLT Supplier: 
XLAM

Glulam Supplier: **HESS**

Mass Timber Installer:  **SAVCON**





Barker College

Barker College
Prep School

Castle Hill

Parramatta

Sydney
Olympic Park

Merrylands

Burwood

Chatswood

Sydney

Manly

Bondi Junction




The building's drawcards include;

- A Dining Commons
- Shaded boardwalk for meals and gatherings,
- A Maths Courtyard for outdoor learning,
- And breakout spaces for student-led small group activities.

Structural materials



- Concrete GF and Level 1
 - Driven by durability requirements and transfer beam
- Mass Timber Level 2 and Roof including bracing and core



Building features

- A contemporary geometric façade expresses the language of mathematics
- An indigenous artwork above the main entrance is illuminated in the evening like the night sky
- The timber structure is exposed from within, deepening the connection to nature while reducing the building's carbon footprint.



Origin of timber

Architectus proposed a hybrid timber framed building at concept stage which established themselves with a point of difference

Biophilia



The architecture is designed to bring the benefits of biophilia to the school community

Sustainability



- **“26% reduction in upfront carbon** compared to a concrete framed building
- **Reduction of 1,092TCO₂eq**, which can be likened to that produced by 130 homes annually,” Stephen Surjan, Buildcorp



Structural floor system






Image source: TTW



Structural system – lateral

- Complex shape required a detailed lateral design



Stairs – Architectural and structural



Image unavailable for publish




Image source: TTW

Stairs - XLAM shop drawing





Image source: XLAM

Stairs: Savcon installation





Supply - Glulam



HESS

- Wood species: Spruce
- Volume: 600 m³ glued laminated timber
- Scope of Services: Planning, Production, Component Delivery
- Transported in 40-foot containers
- Glulam was pre-coated at the factory
- And most of the necessary steel parts have already been assembled.



Supply - CLT



- The **473.9m3 of CLT** used on Barker College Maths Hub Shores was sourced from PEFC certified, sustainable softwood plantations in Southern NSW, Australia and can be **regrown in 44 minutes**. ^{1*}
- XLAM CLT is Declare certified as being **Red List free**, free from adhesive polyurethane formaldehyde and 100% recyclable at the end of life. ^{4*}
- XLAM CLT **panels are optimised by feedstock** strength across their depth, using stronger MGP10 timber in the outer lamellas and lower strength MGP6 timber in the internal layers.
- The feedstock for XLAM CLT is cut by Hyne at their Tumbarumba mill, and the CLT is manufactured at XLAM's factory in Barnawartha. Both companies are a **great supporter of regional employment**, with over 608 people employed across Hyne's 10 sites. On top of that, every direct job at our regional sites supports a further 2 jobs in the local community. ^{5*}



Feasibility & Advisory



Design & Engineering




Planning & Permits



Logistics, Installation & Onsite

Shop drawing CLT






- Hess took the Architectural geometry and modelled to LOD 300.
- XLAM then take the same model and overlay the CLT.
- An iterative process of coordination and reviews brings the documentation to LOD 400
- This model feeds the CNC



How is CLT is made





Summary of CLT manufacture process



Manufacture efficiencies



Waste = 5%
Billet efficiency = 36%



Waste = 4%
Billet efficiency = 63%

- Big panels = *less billets, less lifts, less QA checks, lower cost*

Manufacture efficiencies




Waste = 27%
Billet efficiency = 26%

*Note – nesting of panels is shown as an example only and not representative of the actual panelisation for Barker College Maths Hub.

Manufacture efficiencies – CNC

- Understand tooling = *Cut to +/- 2mm tolerance*
 - Pre-drilling can't be performed at an angle
 - At Barker college they could only drill a 6mm diameter pilot hole, 5mm deep as a starting point
- Avoid panel flipping = *20 minutes per flip*



Shop drawing - transportation



Site Contact: Dave Wilson - dave_wilson@buildcorp.com.au - 61 426 100 246
Site Address: 91 Pacific Highway
 Hornsby, NSW
Ship via port: Local Delivery

All packs with 25mm fillets between panels, wrapped in XLam protective and strapped to bearers
 Packs to have 150mm height bearers





Plugs to be included:
 Untreated: **XX** Treated: **XX**

Wrap tape:
 xx rolls of 300mm x 30m
 xx rolls of 75mm x 30m

OSS items:

Total weight: 18.3 T
Total volume: 54.8 m³



Delivery will be as per this proposed loading so far as reasonably practicable. Load will be amended if required to satisfy any transport/safety concerns raised by the Haulage contractor or any other party of the CoR prior to despatch. Panel weights on this loading document are calculated with a timber density of 530kg/m³ which is based on the upper range of moisture content expected in CLT. The panel weight may increase with an uptake in moisture, and allowance should be made to compensate for this. Discuss with the crane contractor on the allowances to be made to the crane capacity and speak to XLam should you require any further information.


Rev	Date	Modification	Project: 91 Pacific Highway	LOADING - Delivery 3 off 17	Rough XLam volume: 36.7 m ³
			Client: Buildcorp Group Pty Ltd	FOR COMMENT	
				nts	DRW: PK - PR: JL job no: A20108 date: 31/01/2022 sheet no: XL 503 rev. A

Designing for transport

- Understand transport limitations of your route
- Overseas shipping constrained by container sizes
- Within Australia, larger panels are generally still more cost effective

Table 4 - Travel Times

Location	Day	Up to 3.1 m wide and/or 19.0 m long	Up to 3.1 m wide and/or 19.1 m - 22.0 m long	3.2 m - 3.5 m wide and/or 22.1 - 25.0 m long
Wharf Roads, Hume, Princes and Western Freeways	Any day	At all times	At all times	At all times
Rural Areas	Any day	At all times	At all times	Sunrise - sunset
Princes Highway through Geelong Urban Area	Any day	At all times	At all times	9.00 am - 4.00 pm 6.30 pm - 7.00am
Melbourne and Geelong Urban Areas	Monday - Friday (not public holidays)	At all times	9.00 am - 4.00 pm 6.30 pm - 7.00 am	9.00 am - 4.00 pm 6.30 pm - sunset 11.00 pm - 6.00 am
	Saturday, Sunday and public holidays	At all times	11.00 pm - sunset	11.00 pm - sunset



Transportation – Barker College



Image source: Savcon

Assembly

- The demanding lateral system required complex glulam connections
 - Big double knife plates and lots of bolts
 - Dowell connections were all prefabricated leaving only bolted connections on site
- Sequencing
 - The central section of the building had to be constructed first
 - Access was reasonably hard and therefore installation was relatively slow. But still completed in 11 weeks!
 - When panels start changing directions it gets harder
- Weather
 - There was a fair bit of rain but no moisture related issues for the timber
 - The roof was on a 2degree pitch and all joints were double taped.



Image source: Savcon





Image source: Savcon

Advanced Timber Construction Industry: A Review of 350 Multi-Storey Timber Projects





Image Source: Advanced Timber Construction Industry: A Review of 350 Multi-Storey Timber Projects from 2000–2021 by Hana Svatoš-Ražnjević

- Study of 350 contemporary multi-storey timber building projects from 2000 to 2021
- Assesses quantitative and qualitative data including structural system, material, program, massing, spatial organisation.
- Draws a parallel between architectural characterises and their relation to structural systems in timber

Number of Projects per City



Review of 350 Multi-Storey Timber Projects




76.3%
ORTHOGONAL




19.7%
SEMI-ORTHOGONAL



4%
OTHER




79.7%
REGULAR





16.6%
INCREMENTAL HEIGHTS




3.4%
FLOORPLATE VARIATIONS



98.9%
GRID,
GRID-BASED, LINAR ARRAY



1.1%
IRREGULAR



MATERIALS

- all-timber
- timber-concrete
- timber-steel
- timber-concrete-steel
- n/a



Image source: Architectus

Barker College Maths Hub



*Excellence in Timber Design
Commercial Buildings*



Kieran Hayes

Senior Technical Engineer
CPEng MIEAust NER, Passiv
Haus Designer

